

MIAMI-DADE COUNTY, FLORIDA  
MIAMI-DADE WATER AND SEWER DEPARTMENT

FURNISH & INSTALL 8-INCH D.I. WATER MAIN WITHIN ENTRADA NEIGHBORHOOD  
(MATHESON AVE. EAST OF S.W. 37th AVE. INCL. ROGERS RD. & CURTIS LN;  
AND STEWART AVE. EAST OF S.W. 37th AVE.)  
AND LOQUAT AVE. FROM S.W. 37th AVE. TO LINDEN LN. (LINDEN AVE.)

PCTS No. 14590  
PROJECT ER No. W017003

ADDENDUM NO. 1

July 21, 2017

TO ALL BIDDERS:

The Contract Documents for the above referenced project are hereby amended as follows:

1. To the TECHNICAL SPECIFICATIONS, make the following changes:
  - A. To Section 1.00 Scope; after the second paragraph insert the following:

**"The construction estimate (consisting of biddable items) for the Miami-Dade Water and Sewer Department portion of the project is: \$602,833.00. NOTE: THIS AMOUNT DOES NOT INCLUDE A CONTINGENCY ALLOWANCE, OR DEDICATED ALLOWANCES."**
  - B. To Section 3.00 Sequence of Construction and General Information, Subsection A General, Paragraph 16; at the end of the paragraph insert the following:

**"The Department may, at its option, allow for a 100 psi pressure test based on the plan design, condition of the existing system or material limitation."**
  - C. To Section 3.00 Sequence of Construction and General Information, Subsection B Project Notes; after Paragraph 9 insert the following:

**"10. 316 stainless steel tapping saddles with the MJ outlet shall be used on this Project. See Section 5.07.4 Valves - Tapping Sleeve and Valve."**
  - D. To Section 5.07.1 Valves - Air Release Valves (Manual) and Flushing Valve Outlets, Subsection A, Paragraph 2; delete the paragraph in its entirety and substitute therefore:

**"2. Corporation Stops                      1-1/2 inch, ballcorp corporation stop  
(for air release valve)                      AY McDonald 76102-22, Ford FB1000 NL  
or approved equal (rating of 300 psi)"**

E. To Section 5.08 Miscellaneous Materials, Subsection B, Paragraphs 3 and 4; delete the paragraphs in their entirety and substitute therefore:

**"3. Corporation stops  
(chlorination, testing, service)                      1-inch ballcorp corporation stop  
AY McDonald 74701B,  
Ford FB1000-4x,  
or approved equal (rating of 300 psi)**

**4. Corporation stops    1-1/2 x 2-inch ballcorp corporation stop  
(air release valve)    AY McDonald 76102-22,  
Ford FB1000 NL,  
or approved equal (rating of 300 psi)"**

F. To Section 6.15 Cleaning, Testing and Disinfecting, Subsection B Testing, Paragraph 1; at the end of the paragraph insert the following:

**"The Department may, at its option, allow for a 100 psi pressure test based on the plan design, condition of the existing system or material limitation."**

**END OF ADDENDUM NO. 1**



---

Victor M. Rodriguez  
Sr. Construction Specification Writer