




REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
JACKSONVILLE DISTRICT CORPS OF ENGINEERS
MIAMI REGULATORY OFFICE
9900 SOUTHWEST 107th Ave, SUITE 203
MIAMI, FLORIDA 33176

Regulatory Division
South Permits Branch
Miami Regulatory Office
SAJ-1999-02683 (GP-AG)

AUG 08 2013



City of Miami
c/o Orlando Misas, CIP Project Manager
444 SW 2nd Avenue
Miami, FL 33130

Dear Mr. Misas:

Your application for a Department of the Army permit received on April 26, 2013, has been assigned number SAJ-1999-02683. A review of the information and drawings provided shows the proposed work is to constructing a 22.5 foot wide by 155 foot long baywalk/deck as well as a 9 foot wide by 94 foot long connection walkway to an existing walkway at Margaret Pace Park. Of the total 4,033 square feet associated with the structure only 594 square feet will be over navigable waters of the U.S. and the remaining will be located landward of the annual high tide line. The widest portion of the deck will be located at the south property line and will extend over water approximately 12 feet and will be supported by 2 concrete piles. The remainder of the baywalk will vary between 1-4 feet over water and will be cantilever. The project also includes the temporary deployment of a turbidity curtain during the construction phase. Work is proposed in U.S. navigable waters.

The project is located on Biscayne Bay at 1737 North Bayshore Drive in Section 19, Township 53 South, Range 42 East, Miami, Florida 33172.

Your project, as depicted on the enclosed drawings dated by the Corps on August 8, 2013, is authorized by Regional General Permit (GP) SAJ-33. This authorization is valid until **8 April 2018**. You must comply with all of the special and general conditions and any project-specific conditions of this authorization or you may be subject to enforcement action. The following project-specific conditions are included with this authorization:

- 1. Reporting Address:** All reports, documentation and correspondence required by the conditions of this permit shall be submitted to the following address: U.S. Army Corps of Engineers, Regulatory Division, Enforcement Section, 9900 Southwest 107th Avenue, Suite 203, Miami, Florida 33176. The Permittee shall reference this permit number, SAJ-1999-2683 (GP-AG), on all submittals.

2. Commencement Notification: Within ten (10) days from the date of initiating the authorized work, the Permittee shall provide to the Corps a written notification of the date of commencement of work authorized by this permit.

3. Self-Certification: Within sixty (60) days of completion of the authorized work or at the expiration of the construction authorization of this permit, whichever occurs first, the Permittee shall complete the attached “Self-Certification Statement of Compliance” form (attached) and submit to the Corps. In the event that the completed work deviates, in any manner, from the authorized work, the Permittee shall describe, on the Self-Certification Form, the deviations between the work authorized by the permit and the work as constructed. Please note that the description of any deviations on the Self-Certification Form does not constitute approval of any deviations by the Corps.

4. Posting of Permit: The Permittee shall ensure that all contractors, sub-contractors, and entities associated with the implementation of the project review, understand, and comply with the approved plans and special conditions made part of this permit. Complete copies of the permit and approved plans shall be available at the construction site at all times. Failure to comply with the approved plans and permit special conditions may subject the Permittee to enforcement action.

5. Regulatory Agency Changes: Should any other regulatory agency require changes to the work authorized or obligated by this permit, the Permittee is advised that a modification of this permit is required prior to initiation of those changes. It is the Permittee’s responsibility to request a modification from the Miami Regulatory Office.

6. Manatee Conditions: The Permittee shall comply with the “Standard Manatee Conditions for In-Water Work – 2011,” attached to this permit.

7. Sea Turtle and Smalltooth Sawfish Conditions: The Permittee agrees to abide by the enclosed standard construction conditions designed to protect the Smalltooth sawfish and sea turtles (National Marine Fisheries, 2006).

8. Turbidity Barriers: Prior to the initiation of any of the work authorized by this permit the Permittee shall install floating turbidity barriers with weighted skirts that extend to within one foot of the bottom around all work areas that are in, or adjacent to, surface waters. The turbidity barriers shall remain in place and be maintained until the authorized work has been completed and all erodible materials have been stabilized.

9. Water Quality Certification and FWC Licensing: This letter of authorization does not obviate the necessity to obtain any other Federal, State, or local permits, which may be required. Prior to the initiation of any construction, projects qualifying for this Nationwide permit must qualify for an exemption under section 403.813(1), F.S. or 373.406, F.S., or

otherwise be authorized by the applicable permit required under Part IV of Chapter 373, F.S., by the Department of Environmental Protection, a water management district under section 373.069, F.S., or a local government with delegated authority under section 373.441, F.S., and receive Water Quality Certification (WQC) and applicable Coastal Zone Consistency Concurrence (CZCC) or waiver thereto, as well as any authorizations required for the use of state-owned submerged lands under Chapter 253, F.S., and, as applicable, Chapter 258, F.S. You should check State-permitting requirements with the Florida Department of Environmental Protection or the appropriate water management district.

This letter of authorization does not include conditions that would prevent the ‘take’ of a state-listed fish or wildlife species. These species are protected under sec. 379.411, Florida Statutes, and listed under Rule 68A-27, Florida Administrative Code. With regard to fish and wildlife species designated as species of special concern or threatened by the State of Florida, you are responsible for coordinating directly with the Florida Fish and Wildlife Conservation Commission (FWC). You can visit the FWC license and permitting webpage (<http://www.myfwc.com/license/wildlife/>) for more information, including a list of those fish and wildlife species designated as species of special concern or threatened. The Florida Natural Areas Inventory (<http://www.fnai.org/>) also maintains updated lists, by county, of documented occurrences of those species.

10. Cultural Resources/Historic Properties:

- a. No structure or work shall adversely affect, impact, or disturb properties listed in the National Register of Historic Places (NRHP) or those eligible for inclusion in the NRHP.
- b. If during the ground disturbing activities and construction work within the permit area, there are archaeological/cultural materials encountered which were not the subject of a previous cultural resources assessment survey (and which shall include, but not be limited to: pottery, modified shell, flora, fauna, human remains, ceramics, stone tools or metal implements, dugout canoes, evidence of structures or any other physical remains that could be associated with Native American cultures or early colonial or American settlement), the Permittee shall immediately stop all work in the vicinity and notify the Corps. The Corps shall then notify the Florida State Historic Preservation Officer (SHPO) and the appropriate Tribal Historic Preservation Officer(s) (THPO(s)) to assess the significance of the discovery and devise appropriate actions.
- c. A cultural resources assessment may be required of the permit area, if deemed necessary by the SHPO, THPO(s), or Corps, in accordance with 36 CFR 800 or 33 CFR 325, Appendix C (5). Based, on the circumstances of the discovery, equity to all parties, and considerations of the public interest, the Corps may modify, suspend or revoke the permit in accordance with 33 CFR Part 325.7. Such activity shall not resume on non-federal lands without written authorization from the SHPO and the Corps.
- d. In the unlikely event that unmarked human remains are identified on non-federal lands, they will be treated in accordance with Section 872.05 Florida Statutes. All work in the vicinity shall immediately cease and the Permittee shall immediately notify the medical examiner, Corps, and State Archeologist. The Corps shall then notify the appropriate SHPO and THPO(s). Based, on

the circumstances of the discovery, equity to all parties, and considerations of the public interest, the Corps may modify, suspend or revoke the permit in accordance with 33 CFR Part 325.7. Such activity shall not resume without written authorization from the State Archeologist, SHPO and the Corps.

e. In the unlikely event that human remains are encountered on federal or tribal lands, or in situations where Archaeological Resources Protection Act of 1979, or Native American Graves Protection Repatriation Act of 1990 applies, all work in the vicinity shall immediately cease and the Permittee immediately notify the Corps. The Corps shall then notify the appropriate THPO(s) and SHPO. Based, on the circumstances of the discovery, equity to all parties, and considerations of the public interest, the Corps may modify, suspend or revoke the permit in accordance with 33 CFR Part 325.7. After such notification, project activities on federal lands shall not resume without written authorization from the Corps, and/or appropriate THPO(s), SHPO, and federal manager. After such notification, project activities on tribal lands shall not resume without written authorization from the appropriate THPO(s) and the Corps.

11. Best Management Practices: Environmental controls and best management practices must be implemented to properly contain construction materials and prevent fugitive particulates from entering surrounding waters during the construction of the project.

12. Assurance of Navigation and Maintenance: The Permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structures or work herein authorized, or if in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the Permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

If you are unable to access the internet or require a hardcopy of any of the conditions, limitations, or expiration date for the above referenced GP, please contact Albert Gonzalez by telephone at 305-779-6055.

Thank you for your cooperation with our permit program. The Corps Jacksonville District Regulatory Division is committed to improving service to our customers. We strive to perform our duty in a friendly and timely manner while working to preserve our environment. We invite you to take a few minutes to visit <http://per2.nwp.usace.army.mil/survey.html> and complete our automated Customer Service Survey. Your input is appreciated – favorable or otherwise. Again, please be aware this web address is case sensitive and should be entered as it appears above.

Sincerely,



ALBERT GONZALEZ
Project Manager

Enclosures:

FWS Standard Manatee Conditions for In-Water Work (2011)
NMFS Sea Turtle and Smalltooth Sawfish Construction Conditions (2006)
General Conditions
Self-Certification Statement of Compliance
Permit Transfer Request
Project drawings date stamped on 8 August 2013

Copies Furnished:

Ricardo Ayala, BCC Engineering
CESAJ-RD-PE

SELF-CERTIFICATION STATEMENT OF COMPLIANCE

**General Permit Number: SAJ-33
Application Number: SAJ-1999-02683**

Permittee's Name & Address (please print or type): _____

Telephone Number: _____

Location of the Work: _____

Date Work Started: _____ Date Work Completed: _____

Description of the Work (e.g. bank stabilization, residential or commercial filling, docks, dredging, etc.):

Acreage or Square Feet of Impacts to Waters of the United States:

Describe Mitigation completed (if applicable):

Describe any Deviations from Permit (attach drawing(s) depicting the deviations):

I certify that all work, and mitigation (if applicable) was done in accordance with the limitations and conditions as described in the permit. Any deviations as described above are depicted on the attached drawing(s).

Signature of Permittee

Date

GENERAL CONDITIONS

33 CFR PART 320-330

PUBLISHED FEDERAL REGISTER DATED 13 NOVEMBER 1986

1. The time limit for completing the work authorized ends on date identified in the letter. If you find that you need more time to complete the authorized activity, submit your request for a time extension to this office for consideration at least one month before the above date is reached.
2. You must maintain the activity authorized by this permit in good condition and in conformance with the terms and conditions of this permit. You are not relieved of this requirement if you abandon the permitted activity, although you may make a good faith transfer to a third party in compliance with General Condition 4 below. Should you wish to cease to maintain the authorized activity or should you desire to abandon it without a good faith transfer, you must obtain a modification of this permit from this office, which may require restoration of the area.
3. If you discover any previously unknown historic or archeological remains while accomplishing the activity authorized by this permit, you must immediately notify this office of what you have found. We will initiate the Federal and state coordination required to determine if the remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.
4. If you sell the property associated with this permit you must obtain the signature of the new owner in the space provided and forward a copy of the permit to this office to validate the transfer of this authorization.
5. If a conditioned water quality certification has been issued for your project, you must comply with the conditions specified in the certification as special conditions to this permit. For your convenience, a copy of the certification is attached if it contains such conditions.
6. You must allow a representatives from this office to inspect the authorized activity at any time deemed necessary to ensure that it is being or has been accomplished in accordance with the terms and conditions of your permit.

STANDARD MANATEE CONDITIONS FOR IN-WATER WORK

2011

The permittee shall comply with the following conditions intended to protect manatees from direct project effects:

- a. All personnel associated with the project shall be instructed about the presence of manatees and manatee speed zones, and the need to avoid collisions with and injury to manatees. The permittee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing manatees which are protected under the Marine Mammal Protection Act, the Endangered Species Act, and the Florida Manatee Sanctuary Act.
- b. All vessels associated with the construction project shall operate at "Idle Speed/No Wake" at all times while in the immediate area and while in water where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will follow routes of deep water whenever possible.
- c. Siltation or turbidity barriers shall be made of material in which manatees cannot become entangled, shall be properly secured, and shall be regularly monitored to avoid manatee entanglement or entrapment. Barriers must not impede manatee movement.
- d. All on-site project personnel are responsible for observing water-related activities for the presence of manatee(s). All in-water operations, including vessels, must be shutdown if a manatee(s) comes within 50 feet of the operation. Activities will not resume until the manatee(s) has moved beyond the 50-foot radius of the project operation, or until 30 minutes elapses if the manatee(s) has not reappeared within 50 feet of the operation. Animals must not be herded away or harassed into leaving.
- e. Any collision with or injury to a manatee shall be reported immediately to the Florida Fish and Wildlife Conservation Commission (FWC) Hotline at 1-888-404-3922. Collision and/or injury should also be reported to the U.S. Fish and Wildlife Service in Jacksonville (1-904-731-3336) for north Florida or Vero Beach (1-772-562-3909) for south Florida, and to FWC at ImperiledSpecies@myFWC.com
- f. Temporary signs concerning manatees shall be posted prior to and during all in-water project activities. All signs are to be removed by the permittee upon completion of the project. Temporary signs that have already been approved for this use by the FWC must be used. One sign which reads *Caution: Boaters* must be posted. A second sign measuring at least 8 ½" by 11" explaining the requirements for "Idle Speed/No Wake" and the shut down of in-water operations must be posted in a location prominently visible to all personnel engaged in water-related activities. These signs can be viewed at MyFWC.com/manatee. Questions concerning these signs can be sent to the email address listed above.

CAUTION: MANATEE HABITAT

All project vessels

IDLE SPEED / NO WAKE

When a manatee is within 50 feet of work
all in-water activities must

SHUT DOWN

Report any collision with or injury to a manatee:

Wildlife Alert:

1-888-404-FWCC(3922)

Call FWC or #FWC





UNITED STATES DEPARTMENT OF COMMERCE
National Oceanic and Atmospheric Administration
NATIONAL MARINE FISHERIES SERVICE
Southeast Regional Office
263 13th Avenue South
St. Petersburg, FL 33701

SEA TURTLE AND SMALLTOOTH SAWFISH CONSTRUCTION CONDITIONS

The permittee shall comply with the following protected species construction conditions:

- a. The permittee shall instruct all personnel associated with the project of the potential presence of these species and the need to avoid collisions with sea turtles and smalltooth sawfish. All construction personnel are responsible for observing water-related activities for the presence of these species.
- b. The permittee shall advise all construction personnel that there are civil and criminal penalties for harming, harassing, or killing sea turtles or smalltooth sawfish, which are protected under the Endangered Species Act of 1973.
- c. Siltation barriers shall be made of material in which a sea turtle or smalltooth sawfish cannot become entangled, be properly secured, and be regularly monitored to avoid protected species entrapment. Barriers may not block sea turtle or smalltooth sawfish entry to or exit from designated critical habitat without prior agreement from the National Marine Fisheries Service's Protected Resources Division, St. Petersburg, Florida.
- d. All vessels associated with the construction project shall operate at "no wake/idle" speeds at all times while in the construction area and while in water depths where the draft of the vessel provides less than a four-foot clearance from the bottom. All vessels will preferentially follow deep-water routes (e.g., marked channels) whenever possible.
- e. If a sea turtle or smalltooth sawfish is seen within 100 yards of the active daily construction/dredging operation or vessel movement, all appropriate precautions shall be implemented to ensure its protection. These precautions shall include cessation of operation of any moving equipment closer than 50 feet of a sea turtle or smalltooth sawfish. Operation of any mechanical construction equipment shall cease immediately if a sea turtle or smalltooth sawfish is seen within a 50-ft radius of the equipment. Activities may not resume until the protected species has departed the project area of its own volition.
- f. Any collision with and/or injury to a sea turtle or smalltooth sawfish shall be reported immediately to the National Marine Fisheries Service's Protected Resources Division (727-824-5312) and the local authorized sea turtle stranding/rescue organization.
- g. Any special construction conditions, required of your specific project, outside these general conditions, if applicable, will be addressed in the primary consultation.

Revised: March 23, 2006

O:\forms\Sea Turtle and Smalltooth Sawfish Construction Conditions.doc



DEPARTMENT OF THE ARMY PERMIT TRANSFER REQUEST

PERMIT NUMBER: SAJ-1999-02683 (GP-AG)

When the structures or work authorized by this permit are still in existence at the time the property is transferred, the terms and conditions of this permit will continue to be binding on the new owner(s) of the property. Although the construction period for works authorized by Department of the Army permits is finite, the permit itself, with its limitations, does not expire.

To validate the transfer of this permit and the associated responsibilities associated with compliance with its terms and conditions, have the transferee sign and date below and mail to the U.S. Army Corps of Engineers, Enforcement Branch, Post Office Box 4970, Jacksonville, FL 32232-0019.

(TRANSFeree-SIGNATURE)

(SUBDIVISION)

(DATE)


(LOT) (BLOCK)

(STREET ADDRESS)

(NAME-PRINTED)

(MAILING ADDRESS)

(CITY, STATE, ZIP CODE)




**CITY OF MIAMI
CAPITAL IMPROVEMENTS PROGRAM**

**MARK SPANIOLI, P.E. DIRECTOR
PROJECT No. B-30731
MIAMI WOMAN'S CLUB
SEAWALL & BAYWALK
CONSTRUCTION PLANS**

Commission:

Mayor Tomas P. Regalado
Commissioner Wilfredo (Willy) Gort
Commissioner Marc Sarnoff
Commissioner Frank Carollo
Commissioner Francis Suarez
Commissioner Michelle Spence Jones
City Manager Johnny Martinez, P.E.



INDEX OF SHEETS

SHEET NO.	SHEET DESCRIPTION
1	KEY SHEET
2	SUMMARY OF QUANTITIES
3	GENERAL NOTES
4	ENGINEERING PLAN
5	AMENITIES PLAN
6 & 7	ENGINEERING DETAILS
S-1	STRUCTURAL NOTES
S-2	KEY PLAN
S-3 to S-5	PLAN SHEETS
S-6 & S-7	SECTIONS & DETAILS
S-8	CONCRETE REPAIR DETAILS

ONE (1)
PROJECT MANAGER: A. Ayala, P.E.
DATE: 1999-02683

AUG 08 2013

NOTE: THE SCALE OF THESE PLANS MAY
HAVE CHANGED DUE TO REPRODUCTION.

ROADWAY PLANS
ENGINEER OF RECORD: RICARDO A. AYALA, P.E.

P.E. NO.: 69590

SHEET
NO.
1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

1

ITEM PAY ITEM	DESCRIPTION	UNITS	QUANTITY
1. 101-1	MOBILIZATION	LS	1
1. 104-10-3	SILT FENCE	LF	.328
2. 104-11	FLOATING TRIBORI BARRIER	LF	.350
3. 104-11	INLET PROTECTION SYSTEM	EA	2
4. 104-18	CLEARING AND GRUBBING	AC	0.084
5. 110-1-1	EMBANKMENT (FL. TO REGRADE GREEN AREAS ALONG WALKWAY)	CY	6
6. 120-6	CONTECH HYDRODYNAMIC SEPARATION SYSTEM, MODEL CDS2015	EA	1
7. 425-2-101	YARD DRAIN NYLONPLAST (12")	EA	13
8. 425-10	DRAIN BASIN NYLONPLAST (12")	EA	1
9. 425-10	TRIVCFDRAIN (ZURK12-886 OR APPROVED EQUAL)	LF	8
10. 430-175-112	Pipe Culv (Off Water) (Round) 6" (ALL PIPE TO BE PVC)	LF	168
11. 430-175-112	Pipe Culv (Off Water) (Round) 10" (ALL PIPE TO BE PVC)	LF	30
12. 430-175-112	Prestressed Concrete Pipe, 14" Sq.	LF	48
13. 455-34-2	Prestressed Concrete Pipe, 14" Sq.	LF	140
14. 515-2-319	PEDESTRIAN RAILING	LF	143
15. 520-24	CONCRETE DOGSE (NY PETO)	LF	150
16. 550-10-929	FENCING (ALUMINUM PICKET FENCE)	SY	120
17. 570-1-2	PERFORMANCE TURF - SOD	EA	17
18. 580-1-2	LANDSCAPE COMPLETE (CABBAGE PALM OR EQUAL)	SF	150
19.	SEAWALL REPAIR	SF	510
20.	RIVER ROCK	CY	132
21.	CAST-IN-PLACE CONCRETE	LF	450
22. 715-2-11	LIGHTING - CONDUIT UNDERGROUND	EA	5
23. 715-14-32	LIGHTING - PULL BOX INSTALL	EA	3
24. 715-511-115	LIGHT POLE COMPLETE SPECIAL DESIGN (15' HI. FL.)	EA	4
25. 721-75-1	SCRAP (AS PER CITY OF MIAMI GREENWAY STANDARDS)	EA	2
26. 721-74-1	TRASH RECEPACLE (AS PER CITY OF MIAMI GREENWAY STANDARDS)	EA	2

PAY ITEM NOTES:

PAY ITEM INCLUDES ESTIMATED QUANTITY CONTINGENT UPON FIELD CONDITIONS AND MAY BE INCREASED OR DECREASED AS DIRECTED BY THE ENGINEER.

CLEARING AND GRUBBING INCLUDES REMOVAL OF EXISTING PAVEMENT, MISCELLANEOUS CONCRETE (SEAWALL DEMOLITION), VEGETATION, TREES AND DEBRIS TO BE DISPOSED OF IN LEGAL AREAS PROVIDED BY THE CONTRACTOR, INCLUDES THE COST OF CLEANING OUT ALL EXISTING DRAINAGE STRUCTURES WHICH ARE TO REMAIN WITHIN THE LIMITS OF CONSTRUCTION.

THIS PAY ITEM SHALL INCLUDE FURNISHING AND INSTALLING COMPLETE HYDRODYNAMIC DEVICE AS SPECIFIED IN THE PLANS (CONTech HYDRODYNAMIC SEPARATION SYSTEM- MODEL No. CDS2015). INSTALLATION OF HYDRODYNAMIC DEVICES SHALL COMPLY WITH THE MANUFACTURER'S RECOMMENDATIONS AND SPECIFICATIONS AND WITH FOOTNOTES. SECTION 25 FOR INSTALLATION OF MANHOLES.

US ARMY CORPS OF ENGINEERS

AUG 08 2013

MIAMI REGULATORY OFFICE

COE # 1999-02683
PROJECT MANAGER: A. Gonzalez

No. 00500



REVISIONS		DESCRIPTION		DATE BY	PROJECT ID	SHEET NO.
DATE	REV.	DESCRIPTION	BY			

License No. 09950	Capitol Improvement Program
7320 N Kendall Drive, Suite 100 Miami, Florida 33156 Phone: (305) 670-2350 Fax: (305) 670-2351	Project Name: MIAMI WOMAN'S CLUB Contractor's Name: A. Gonzalez Certification of Authorization No. 7194
	B-30731

SUMMARY OF QUANTITIES

2

GENERAL NOTES

**US ARMY
CORPS OF ENGINEERS**

AUG 08 2013

MIAMI REGULATORY OFFICE

COE #: 1999-02683
PROJECT MANAGER: A. Gonzalez

GENERAL NOTES				SHEET NO. 3
<p align="center">CITY OF MIAMI</p> <p align="center">CAPITAL IMPROVEMENTS PROGRAM</p>				
Ricardo A. Aguil, P.E. License No. 38560				PROJECT NAME MIAMI WOMAN'S CLUB SEAWALL & BAYWALK
7300 N. Kendall Drive, Suite #400 Miami, Florida 33156 Phone: (305) 670-2300 Fax: (305) 670-2381 Certificate of Appropriation No. 7194			DATE 07/01/01	REVISIONS DESCRIPTION DATE BY DESCRIPTION
				

**US ARMY
CORPS OF ENGINEERS**

TOTAL PROJECT AREA	4033 SF
TOTAL PROJECT AREA ABOVE WATER	594 SF
TOTAL PROJECT AREA LANDSIDE	3438 SF

CITY OF MIAMI
MARGARET PLACE PARK
1775 N. BAYSHORE DRIVE
MIAMI, FLORIDA 33132

TENNIS COURT

AUG 08 2013

MEET & MATCH
EXIST. GROUND
PROJECT MANAGER: A. Gonzalez

MIAMI REGULATORY OFFICE

1999-02683

MEET & MATCH


EXIST.

PROJECT

MANAGER

A. Gonzalez

NO. 00650



NOTES FOR FIELD CHECKER
NOTES FOR FIELD CHECKER

MIAMI WOMAN'S CLUB
1737 N. BAYSHORE DRIVE
MIAMI, FLORIDA 33132




SILT FENCE

8 LF-2896 PERMA-TRENCH

TYPE 'D' CURB

END TYPE 'D' CURB

COTG RE=5.95-
LE=2.62




**US ARMY
CORPS OF ENGINEERS**

AUG 08 2013

MIAMI REGULATORY OFFICE
COE # 1999-02683
PROJECT MANAGER: A. Gonzalez

MARGARET PAGE PARK
1717 N. BAYSHORE DRIVE




GRAPHIC SCALE
SCALE: N.T.S.
0 10 20
feet

BISCAYNE BAY

KEY PLAN
N.T.S.

REVISIONS		DATE	BY	DESCRIPTION	CITY OF MIAMI	CAPITAL IMPROVEMENTS PROGRAM	PROJECT ID	KEY PLAN	SHEET NO.
DATE	REV.	DESCRIPTION			Steven Goldstein, P.E. License No. 414286 7200 N Kendall Drive, Suite 400 Miami, Florida 33156 Phone: (305) 477-0331	MIAMI WOMAN'S CLUB SEAWALL & BAYWALK	B-30731		S-2
					Engineering Certificate of Authorization No. 7184				

MATCH LINE SEE SHEET S-4




**US ARMY
CORPS OF ENGINEERS**

MANI REGULATORY OFFICE

COE #: 1999-02683
PROJECT MANAGER: H. Gonzalez

AUG 08 2013



GR-
SC-
0

STEVE L. LICEN\$E NO. 44423

1

GRAPHIC SCALE
SCALE: N.T.S.
4.
Feet

A small compass rose icon with the letter 'N' at the top.

1

PLAN N.
N.T.S.

三

ARMY
OF ENGI-

CORP

REVISIONS		DATE	BY	DESCRIPTION	CITY OF MIAMI CAPITAL IMPROVEMENTS PROGRAM		PROJECT ID	NO.
DATE	REV.				P.E. License No. 44423	Steven Goldstein	MIAAMI WOMAN'S CLUB SEAWALL & BAYWALK	B-30731
					7300 N Kendall Drive, Suite 400 Miami, Florida 33139 Phone: (305) 675-0550 Fax: (305) 675-2555			S-3
					Continuation of Authorization No. 7184			
PLAN No. 1								


MARGARET PAGE PARK
1755 BAYSHORE DRIVE
MIAMI, FLORIDA 33132

U.S. ARMY
CORPS OF ENGINEERS



AUG 08 2013

MIAMI REGULATORY OFFICE

COE # 1999-02683
PROJECT MANAGER: A. Gonzalez




MATCH LINE SEE SHEET S-4



2
3 PLAN No. 3
N.T.S.

DATE	BY	DESCRIPTION	REVISIOnS	DATE	DESCRIPTION	CITY OF MIAMI	CAPITAL IMPROVEMENTS PROGRAM	PLAN No. 3	SHEET NO.
						Steven Goldstein P.L. License No. 44423 7300 N Kendall Drive, Suite 400 Miami, Florida 33136 Phone: 305-670-2550 Fax: 305-670-2551 Engineering Certificate of Authorization No. 7184	PROJECT NAME: MIAMI WOMEN'S CLUB B-30731 SEAWALL & BAYWALK		S-5



**US ARMY
CORPS OF ENGINEERS**

AUG 08 2013

REGULATORY OFFICE

COE #: 744-060
PROJECT MANAGER: A. Gunzenhauser

